9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Public Health will be final and legally binding.

Estimate of the approximate quantities for the work of constructing drains in Hassan Town.

No.	Items of work	Unit	Quantity
1	Constructing silk pattern drains with 3″ to 4″ thick slabs dressed for the checks and cement concrete 1 : 2 : 4 for the sides and bed and 1½″ thickness over 3″ thick surki concrete (1 : 2) bed and surface plastered with ½″ cement mortar in the proportion of 1 : 3 and cement pointing the stone slabs including earthwork, etc., complete as per design		
	Design of 3″ section	R.ft.	3,674
2	Do 4″(2) do	,,	760
3	Do 3″ section with old slabs get by dismantling old drains including conveying, splitting, dressing and fixing, etc., complete ..	,,	3,114
4	Constructing 3″ section semi-Rsg. top drains with cement concrete in the proportion of 1 : 2 : 4 on 3″ surki concrete bed and surface plastered with ½″ thick cement mortar in the proportion of 1 : 3 including earthwork, etc., complete as per design	R.ft.	280
5	Constructing |__ shaped drain with 1½ feet width of 3″ thick burnt stone slabs for the bed and side over 9″×4½″ surki concrete bed at the vertex of the angle with cement concrete fillet for the joint including cement pointing the stone slabs and earthwork, etc., as per design	,,	4,540

N. KRISHNIENGAR,
Sanitary Engineer.

GOVERNMENT CENTRAL HIGH SCHOOL, BANGALORE CITY.

Notification dated 8th February 1939.

The undermentioned articles will be auctioned in the premises of the Governemnt Central High School, Bangalore City at 10-30 A.M. on Saturday the 25th February 1939.

The articles will be put up for auction singly or in lots as may be found convenient at the time.

The articles will be knocked down to the highest bidder who will have to pay the whole amount of the bid on the spot and remove the articles after the auction is over.

The decision on any question that may arise shall vest in the Officer-in-charge of the auction.

1.	Iron parts of reversible desk	A few pieces.
2.	Chairs	6 Broken.
3.	Map racks	3 do
4.	Rubber stamps	6
5.	Clock	1
6.	Stool	1
7.	Locks of various sizes	20
8.	Calling bell	1
9.	Easil	1

M. S. RAJAGOPALA RAO,
Head Master.

GOVERNMENT OF MYSORE—ELECTRICAL DEPARTMENT.

Notification No. G. N. 36, dated 11th February 1939.

To

The Firms dealing in brass and hardware materials.

DEAR SIRS,

Please quote your lowest rates for the following materials to be delivered f.o.r., Mysore, and the earliest time of delivery :—

(1) Heavy gauge 1″ Brass Pipe or conduit with coupling at one end and threaded at both ends, in standard lengths of 16 ft. each .. .. 1,300 ft.

Note.—Rate should be quoted on length basis (*i.e.*, so much per R.ft.) and not on weight basis.

(2) Full bends for the above 1" brass pipe or conduit .. .. 50 Nos.
(3) Spare couplings for the above 1" brass pipe or conduit .. .. .. 30 „

Samples will have to be sent, free of charge, if required.

Withdrawal from the quotation after it is accepted will entail cancellation of the order and purchases being made at your expense from other sources.

The undersigned reserves to himself the right to refuse the lowest or any tender whole or part, without assigning any reason therefor.

The latest date for receiving the tenders is 4th March 1939, 12 noon.

The covers containing the tender should be superscribed "Tender for brass pipe, etc., due at 12 noon on 4th March 1939."

Yours faithfully,
M. HAYATH,
For *Chief Electrical Engineer.*

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, BANGALORE.

Abstract Notification.

Subject :—TENDER FOR CARTING 510 BALIGA POLES AND SUNDRY MATERIALS TO KUNIGAL TOWN.

Attention is drawn to this office notification dated 30th January 1939, inviting tenders for the above work, published in Part VI, page 239 of the *Mysore Gazette*, dated 2nd February 1939. The last date of receiving tenders is 17th February 1939 and the earnest money required is Rs. 50.

C. R. GOWDA,
Superintendent.

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, MYSORE.

Abstract Notification dated 12th January 1939.

Attention of the public is invited to the detailed notification dated 12th January 1939, in connection with the installation of the lights, etc., to the District Offices, Mandya, appearing on pages 240-241, of Part VI of the *Mysore Gazette, dated* 2nd February 1939.

Abstract Notification dated 12th January 1939.

Attention of the public is invited to the detailed notification dated 12th January 1939, in connection with the installation of "A" Electric lights, etc., "B" Heating circuit, etc., to the extension of the Anatomy Block at Medical College, Mysore, published on pages 241-244, of Part VI of the *Mysore Gazette,* dated 2nd February 1939.

Notification dated 9th February 1939.

1. Sealed tenders in triplicate will be received in the Office of the Superintendent, Power and Lighting, Mysore, superscribed with the name of the work mentioned below.

2. The plans connected with the work may be seen at the Office of the undersigned at all working hours. The copy, if required, will be made available on payment of Rs. 3 per set.

3. The tenders should be drawn up strictly in conformity with the specifications furnished, writing out the rates at which each item of work will be executed in figures as well as in words failing which no cognisance will be taken of the tender. No items other than those noted in the statement should be included as the items cover provision for all sundries, repairs to damaged masonry and painting.

4. The materials to be used on the work should be of best quality conforming to the specification of this Department and B. S. or A. I. E. E. specification. Mention should also be made of the manufacture and the catalogue numbers of the materials offered. Teak wood planks to be used on the work should be free from knots, cracks and well seasoned. No planks less than 12" in width will be permitted to be used unless it is to make up the difference in size of the board required. Only the lap joints should be adopted in all cases. Lamp holders, ceiling roses, etc., should be of reinforced bakelite material.

5. The undersigned reserves the right to reject the tenders without assigning any reason therefor.

6. The successful tenderer will be required to deposit an earnest money of Rs. 50 (Fifty) in the case of 'A' and Rs. 30 (Thirty) in the case of 'B' and execute an agreement within two days from the date of intimation of acceptance of the tender. He should send samples of all the materials required for the work mounted on a board and start the work after obtaining the approval of the undersigned and with regard to the same and carry out the wiring following the rules of this department as well as that of the Institution of Electrical Engineers. He should also be prepared to adopt any change in the location of control points and other outlets that might be suggested by the undersigned during the progress of the work without extra cost if the tender is not materially affected by such deviations. It should also be noted that the control switches, etc., should be grouped and installed in inconspicuous corners.

7. The undersigned reserves the right also to reject the work either in full or in part if he finds the work not carried out in terms of the specifications or is otherwise dissatisfied with the workmanship.

8. *Names of works.*—'A'—Installing electric lights, etc., to the extension of controller of Stores Office near Central Stores, Mysore State Railway.

'B'—Installing yard lights at Central Store yard, Mysore State Railway.

9. *Last date and time of receiving the tender.*—4th March 1939 at 3 P.M.

10. *Date and time of opening the tender in public.*—4th March 1939 at 4 P.M.

11. A period of 4 weeks will be allowed for the completion of the work in all respects, from the date of final acceptance of the tender. A penalty of R. 10 (ten only) for each day of delay over the stipulated period for completion of the work during the 1st week and Rs. 20 (twenty) in the 2nd week will be enforced. If there be further delay, the department will take charge of the installation at whatever stage it might be and arrange for the completion entirely at the risk of the tenderer.

12. The firm executing the work should arrange, while handing over the installation to this Department to pass a certificate of guarantee for the continuance of satisfactory service to the installation, for a period of 12 calendar months from the date of handing over charge to this Department, while uninterrupted power supply is maintained. Further it will be obligatory on the part of the firm to attend to any defects in the installation that might arise due to bad work during the above period without any return for service rendered.

13. *Details of work.*—The quantities given in the annexed statements A and B are not guaranteed and are subject to variation at the time of executing the work.

'A'

Installing Electric lights to the extension of the Controller of Stores Office, near Central Stores, Mysore State Railway, Mysore.

No.	Particulars	Unit	Quantity
	Part I—Exterior work.		
1	Supplying and running mains single phase in ¾″ W. I. pipe with bends, clamps, etc., using No. 7/·044 SWG. 660 volts grade insulated wire and accessories	R.ft.	35
2	Supplying, fixing and wiring teak wood board 24″×18″×1″ with batters and rear board, equipping it with D. P. S. T. 30 amp. iron clad switches with fuses, one six-way D. P. H. O. pattern 10 amp. per way distribution box in iron case, with 10 amps. circuit switches with bakelite cover, using No. 7/·044 SWG. 660 volts grade insulated wire with accessories	No.	1
3	Earthing	L. S.	
	Part II—Interior Wiring.		
1	Supplying, fixing and wiring in T. W. 2-way 2″×1″ casing treated with 2 coats of shellac varnish for ceiling fans complete with "Bharat" ceiling fans 220 volts, 60 cycles, A. C. with 3 curved aluminium blades canopy, suspension hook, down rod, 5 point variable choke type regulator provided beneath it, one Ivanhoe Trojan lighting unit, complete with B. C. lamp holder 12″ opal ceiling rose, 5 amp. bakelite control switch No. 3/·036 SWG. 250 volts grade insulated wire and accessories	No.	3
2	Do do do as per above specification making use of the ceiling fan with regulator only available in the old office block	,,	1
3	Supplying, fixing and wiring in T. W. 2-way 2″×1″ casing treated with two coats of shellac varnish for ceiling fan and lighting outlet using one Ivanhoe Trojan lighting unit complete with B. C. lamp holder, 12″ opal glass ware. 3-plate bakelite ceiling rose 5 amp. bakelite control switch No. 3/·026 SWG. 250 volts grade insulated wire with accessories	,,	1
4	Do do do for oxidised copper brackets 6″×½″ with O. C. B. C. lamp holder, etc., as per specification above	,,	2
5	Do do do for reinforced bakelite back plate type B. C. lamp holder, etc., as per specification above	,,	4
6	Do do do for combined wall plug and switch 5 amps. with nipple, as per specification above	,,	1
7	Supplying and fixing white opal shades 10″×5″	,,	2
8	Do white opal globe 6″×3¼″ with gallery	,,	4

No.	Particulars	Unit	Quantity
	Part III—Installation of calling bells.		
1	Supplying, fixing and wiring a bell transformer 220 volts to 8, 16, 24, volts, 60 cycles, on a suitable board controlled by a D. P. linked 5 amp. witch protected by a pair of fuses, using necessary accessories ..	No.	1
2	Supplying, fixing and wiring call bells, controlled from two different points using suitable special casing twin conductor, bell wire, call pushes, and accessories	,,	3

'B'

Installing yard lights at Central Store Yard, Mysore State Railway, Mysore.

1	Supplying and running single phase sub-mains from the main board to the sub-distribution board in the verandah of the stores in 2″×1″ T. W. 2-way casing treated with two coats of shellac varnish, using No. 7/.064 SWG. insulated wire and accessories	R.ft.	45
2	Supplying, fixing and wiring, S. P. 50 amps. iron-clad service cut outs on the main board at the tapping point for the sub-main, using No. 7/.064 SWG insulated wire and accessories	No.	2
3	Supplying and running circuit mains for feeding five yard lights on the southern wing in T. W. 2-way casing 2″×1″ treated with 2 coats of shellac varnish, using No. 7-.036 SWG. insulated wire and accessories..	R.ft.	140
4	Do do three yard lights on the northern wing, using No. 7/.029 SWG. insulated wire and accessories	,,	40
5	Supplying and running circuit mains in ¾″ W. I. pipe with bends, clamps, etc., using No. 7/.036 SWG. insulated wire and accessories	,,	25
6	Do do in ½″ W. I. pipe using No. 7/.029 SWG. insulated wire and accessories	,,	25
7	Supplying, fixing and wiring 15 amps. D. P. iron clad switches with fuses, on suitable T. W. boards using No. 7/.036 SWG. insulated wire and accessories	,,	1
8	Do do 10 amp. D. P. iron clad switch with fuses, using No. 7/.029 SWG. insulated wire and accessories	,,	1
9	Erecting and tarring S. M. Rails to be supplied by the Railway Department	,,	9
10	Supplying and fixing 2-pin double cross arm complete with clamp, bolt, etc.	,,	9
11	Do do single cross arm complete with clamps, bolts, etc.	,,	2
12	Supplying and fixing insulators with pins	,,	40
13	Do do Guy sets with anchor rod, 7-strand guy wire and 6 ft. of 2″ galvanised guard pipe	,,	5
14	Supplying and stringing bare copper wire No. 8 B. & S. hard-drawn ..	Lbs.	90
15	Supplying, fixing and wiring goose neck fittings complete with clamp, aluminium hood, B. C. lamp holder, Radial wave reflectors, etc., using No. 3/.036 SWG. insulated wire, and accessories	No.	8
16	Earthing	..	Two

N. B.—The insulated wires to be used should be of 660 volts grade.

M. M. ALI KHAN,
Superintendent.

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, BHADRAVATI.

Abstract Notification dated 9—10*th February* 1939.

The attention of the public is drawn to the Notification, advertised in the *Mysore Gazette,* dated 9th February 1939, page 287, Part VI, for the work of Installing Lightning Conductors to the Male and Female Dispensaries at Sagar, Shimoga District.

The last date of receiving tenders in this Office is 3rd March 1939.

K. SUBBA RAO,
Superintendent.